



**PHASE 2**

**PHASE 1**

Key:

	Excavate to 225mm depth, lay geotextile membrane, 150mm Type 1 sub-base, AC20 dense bin 160/220 at 50mm thick, AC6 dense surf 160/220 at 25mm thick
	Kerbing (half battered, bullnosed dropped, taper) and footway edging
	Slab backing 600 x 600mm
	Existing gully
	Ironwork on site
	Finger post

- Notes:
1. Delivery temperatures to conform to BS EN 13108 Table A.1.
  2. All vertical faces of kerbs, edgings, ironwork and similar projections are to be cleaned and painted with a thin uniform coating of hot applied 40/60 or 70/100 paving grade bitumen.
  3. All kerbing and surfacing to be in accordance with attached specification.
  4. All works to conform to Specification of Highway Works except where amended by Somerset Highways work contract.

	Somerset County Council County Hall Taunton Somerset TA1 4DY Tel: 0300 123 2224 www.somerset.gov.uk	© Crown copyright and database rights 2018 Ordnance Survey 100038362. You are permitted to use this data solely to enable you to respond to, or interact with, the organisation that provided you with the data. You are not permitted to copy, sub-licence, distribute or sell any of this data to third parties in any form.
	Drawing Originator <b>SKANSKA</b>   Infrastructure Services Transport House Crown Industrial Estate Taunton Somerset TA2 8QY Tel: +44 (0)1823 285825	

THIS DRAWING IS COPYRIGHT OF SKANSKA UK LIMITED AND SHALL NOT BE REPRODUCED WITHOUT PRIOR WRITTEN PERMISSION

Drawing Status  
**FOR CONSTRUCTION**

Project Name  
TI004314 A358  
Norton Fitzwarren

Title  
Footway Works - Overview  
1 of 6

Scale NTS	Drawn by DH	Checked by DH	Approved by VN
	Drawn Date 04-11-19	Checked Date 04-11-19	Approved Date 04-11-19

Drawing Number	Revision
TI004314.001	