



Key:

- Excavate to 225mm depth, lay geotextile membrane, 150mm Type 1 sub-base, AC20 dense bin 160/220 at 50mm thick, AC6 dense surf 160/220 at 25mm thick
- Kerbing (half battered, taper) and footway edging
- Footway edging to be removed.
- Ironwork on site, to be adjusted
- Street Lighting Column
- Illuminated Sign

- Notes:**
1. Delivery temperatures to conform to BS EN 13108 Table A.1.
 2. All vertical faces of kerbs, edgings, ironwork and similar projections are to be cleaned and painted with a thin uniform coating of hot applied 40/60 or 70/100 paving grade bitumen.
 3. All kerbing and surfacing to be in accordance with attached specification.
 4. All works to conform to Specification of Highway Works except where amended by Somerset Highways work contract.

Rev B Kerbing ammended. 03/01/20

Rev A Footway alignment ammended. 23/12/19

Client: Somerset County Council
 County Hall
 Taunton
 Somerset
 TA1 4DY
 Tel: 0300 123 2224
 www.somerset.gov.uk

© Crown copyright and database rights 2018 Ordnance Survey 100038382. You are permitted to use this data solely to enable you to respond to, or interact with, the organisation that provided you with the data. You are not permitted to copy, sub-licence, distribute or sell any of this data to third parties in any form.

Drawing Originator:

SKANSKA | Infrastructure Services

Transport House
 Crown Industrial Estate
 Taunton
 Somerset TA2 8QY
 Tel: +44 (0)1823 285825

THIS DRAWING IS COPYRIGHT OF SKANSKA UK LIMITED AND SHALL NOT BE REPRODUCED WITHOUT PRIOR WRITTEN PERMISSION

Drawing Status:
 FOR CONSULTATION

Project Name:
 T1004351 Priorswood Road
 Cheddon Fitzpaine

Title: Original drawing sheet is A3

Proposed Footway Plan

Scale 1 : 250	Drawn by BA	Checked by DH	Approved by VN
	Drawn Date 23-12-19	Checked Date 23-12-19	Approved Date 23-12-19

Drawing Number T1004351.001	Revision B
--------------------------------	---------------